

PROPOSED ADDITIONS AND ALTERATIONS WORKS FOR OFFICE OF FOOTBALL ASSOCIATION OF SINGAPORE @ 100 TYRWHITT ROAD, JALAN BESAR STADIUM, SINGAPORE 207542

SUMMARY OF BILL NO. 3 - OPTIONAL WORKS

ITEM	DESCRIPTION	AMOUNT (S\$)
A	STADIUM REPAINTING WORKS	
B	TUNNEL REPAINTING / RE-TILING / GRAPHIC WORKS	
C	MAIN BLOCK LEVEL 2 RIGHT WING TOILETS (MALE / FEMALE)	
D	MAIN BLOCK LEVEL 2 LEFT WING TOILETS (MALE / FEMALE)	
E	ANNEX BLOCK LEVEL 3 SHOWER / TOILETS (MALE / FEMALE/ HANDICAP)	
F	ANNEX BLOCK LEVEL 4 TOILETS (MALE / FEMALE / HANDICAP)	
	TOTAL AMOUNT OF BILL 3 - OPTIONAL WORKS TO BE CARRIED FORWARD TO SUMMARY OF TENDER	

PROPOSED ADDITIONS AND ALTERATIONS WORKS FOR OFFICE OF FOOTBALL ASSOCIATION OF SINGAPORE @ 100 TYRWHITT ROAD, JALAN BESAR STADIUM, SINGAPORE 207542

BILL NO. 2 - SCHEDULE OF OPTIONAL WORKS

ITEM	DESCRIPTION	UNIT	AMOUNT (S\$)
A	STADIUM REPAINT WORKS		
A1	Supply labour, tools and equipment to prepare and plaster all existing walls including all necessary cleaning and making good surfaces prior to the application of new paint works for stadium interiors only (All walls @ grand stand and gallery stand and 2 side walls surrounding the field).	sum	
A2	Supply and apply 1 under coat and minimum 2 finishing coat of various selected weatherproof paint colour to all wall surface areas and services.	sum	
A3	Supply and apply 1 under coat and minimum 2 finishing coat of various selected exterior metal and wood enamel paint colour to all timber doors, panels, metal railing, grilles, steel structure and etc.	sum	
A4	<p>ANY OTHER WORKS</p> <p>Contractor to price for all other and necessary works (that have been inadvertently left out in the above scope of works) which area deem necessary for the full and proper completion of the project.</p> <p>Please specify below :- (Attached a separate sheet if space is in sufficient)</p> <p>a. _____</p> <p>b. _____</p> <p>c. _____</p>	sum sum sum	
	Total for Stadium Painting Works		

PROPOSED ADDITIONS AND ALTERATIONS WORKS FOR OFFICE OF FOOTBALL ASSOCIATION OF SINGAPORE @ 100 TYRWHITT ROAD, JALAN BESAR STADIUM, SINGAPORE 207542

BILL NO. 2 - SCHEDULE OF OPTIONAL WORKS

ITEM	DESCRIPTION	UNIT	AMOUNT (S\$)
B	STADIUM REPAINT WORKS		
B1	Supply labour, tools, transport and equipment to demolish/ dismantle/ hack away and remove, including all necessary disposal offsite, all unwanted existing <u>floor finishes</u> .		
B2	Supply labour and materials to re-screed existing floor areas c/w necessary waterproofing system and trowelled smooth of surface to received new floor finishes.	sum	
B3	Supply and install new anti-slip floor tiles for Tunnel flooring c/w matching pointing, any necessary waterproofing system and slope to fall.	sum	
B4	Supply labour, tools and equipment to prepare and plaster all existing walls including all necessary cleaning and making good surfaces prior to the application of new paint works for tunnel interiors only.	sum	
B5	Supply and apply 1 under coat and minimum 2 finishing coat of various selected weatherproof paint colour to all wall surface areas and services.	sum	
B6	Supply and apply 1 under coat and minimum 2 finishing coat of various selected exterior metal and wood enamel paint colour to all timber doors, metal railing, grilles, etc.	sum	
B7	Graphic Designer fee to work out graphic poster design base on theme given by Interior Designer. (Cost include any fee payable for usage of stock-pictures by the graphic designer to come out with the poster design) The design is subjected to comments by End-User with request for amendments / changes up to a maximum of 3 times.	sum	
B8	Supply and install new vinyl sticker with water-resistant printing base on design by graphic Designer under item B7 for all phenolic cabinet doors. (Cost of A3 size art work / mock-up print on vinyl sticker shall be provided for confirmation by End User)	sum	

PROPOSED ADDITIONS AND ALTERATIONS WORKS FOR OFFICE OF FOOTBALL ASSOCIATION OF SINGAPORE @ 100 TYRWHITT ROAD, JALAN BESAR STADIUM, SINGAPORE 207542

BILL NO. 2 - SCHEDULE OF OPTIONAL WORKS

ITEM	DESCRIPTION	UNIT	AMOUNT (S\$)
<p>B</p> <p>B9</p>	<p>STADIUM REPAINT WORKS</p> <p>ANY OTHER WORKS</p> <p>Contractor to price for all other and necessary works (that have been inadvertently left out in the above scope of works) which area deem necessary for the full and proper completion of the project.</p> <p>Please specify below :- (Attached a separate sheet if space is in sufficient)</p> <p>a. _____</p> <p>b. _____</p> <p>c. _____</p>	<p>sum</p> <p>sum</p> <p>sum</p>	
	<p><i>Total for Tunnel Upgrading Works</i></p>		

PROPOSED ADDITIONS AND ALTERATIONS WORKS FOR OFFICE OF FOOTBALL ASSOCIATION OF SINGAPORE @ 100 TYRWHITT ROAD, JALAN BESAR STADIUM, SINGAPORE 207542

BILL NO. 2 - SCHEDULE OF OPTIONAL WORKS

ITEM	DESCRIPTION	UNIT	AMOUNT (S\$)
C	MAIN BLOCK LEVEL 2 RIGHT WING TOILETS (MALE / FEMALE)		
C1	Supply labour, tools, transport and equipment to demolish/ dismantle/ hack away and remove, including all necessary disposal offsite, all unwanted existing <u>floor, walls, ceiling elements / fittings</u> and services to facilitate the construction of proposed new works for the respective phases of construction works.		
C2	Supply and install 150mm thick built-on-edge celcom (light weight block) walls of various height c/w cement plastering on both sides; necessary bonding ties, vertical and horizontal steel stiffener / lintel as shown on drawings	sum	
C3	Supply and install 12mm thick calcium silicate board plaster ceiling for wet areas as shown on drawings.	sum	
C4	Make good existing timber door ; finish in specified laminate including new <u>conceal door closer</u> , lever lockset with master key system and repaint existing hardwood door jamb in spray paint finish as shown on drawings.	sum	
C5	Supply labour, tools and equipment to prepare and plaster all new and existing wall / partitions including all necessary cleaning and making good surfaces prior to the application of new paint works as shown on drawings.	sum	
C6	Supply and apply 1 under coat and minimum 2 finishing coat of various selected weatherproof paint colour to all internal wall / ceiling surface areas as shown on drawings.	sum	
C7	Supply and install new wall tiles for selected wet areas areas c/w matching pointing and any necessary waterproofing up-turn system (All wall surfaces to be covered with tiles including surfaces behind cabinet carcasses)	sum	
C8	Supply labour and materials to re-screed existing floor areas c/w necessary waterproofing system and trowelled smooth of surface to received new floor finishes. Cost include 10 years warranty for waterproofing of the wet areas.(Ponding test to be carried out at all wet areas for minimum 24hrs and witness by PM)	sum	
C9	Supply and install new floor tiles for wet areas areas c/w matching pointing, any necessary waterproofing system and slope to fall. (All floor surface in the above areas including cabinet plinths below cabinet carcasses to be covered with tiles)	sum	

PROPOSED ADDITIONS AND ALTERATIONS WORKS FOR OFFICE OF FOOTBALL ASSOCIATION OF SINGAPORE @ 100 TYRWHITT ROAD, JALAN BESAR STADIUM, SINGAPORE 207542

BILL NO. 2 - SCHEDULE OF OPTIONAL WORKS

ITEM	DESCRIPTION	UNIT	AMOUNT (S\$)
C	MAIN BLOCK LEVEL 2 RIGHT WING TOILETS (MALE / FEMALE)		
C10	Supply and install Phenolic board toilet cubicles c/w phenolic boards cubicles and accessories for Male and Female Toilets.	sum	
C11	Supply and install new Door Sign base on Designer's Theme for all internal Doors.Provision of art work for approval by Client; Fabrication / Installation of actual signage on doors.	sum	
C12	Supply and install Vanity cabinet with Mirror including Solid surface top and laminate carcass for Male / Female. (2 sets)	sum	
C13	Supply, delivery and installation of new stainless steel cold-water pipe works c/w private water meter for each pantry, check valves, gate valves, ball valves, water filter and all accessories.	sum	
C14	Supply and install floor wastes, floor traps and connect to sanitary waste pipe located at floor below c/w coring, supports, pipework & fittings as required.	sum	
C15	Supply and install following approved sanitary wares fixtures and fitting c/w all sanitary and plumbing piping works; brackets; and accessories as follow: <u>Male / Female / Handicap Toilet</u> <ul style="list-style-type: none"> * Selected seating type water closet with sensor flush * Selected wall hung wash basin for handicap Toilet * Selected standard size recessed wash basin for vanity counter for both Male & Female Toilets. * Selected sensor water tape for vanity basin for Male, Female & Handicap Toilets * Selected jumbo toilet paper holder * Selected auto sensor hand soap dispenser * Selected hand dryer * Selected bidget spray * Selected standard mirror for handicap toilet. * Selected standard handicap rail bar set * Selected bid tap for washing of toilet. 	sum	
C16	To supply and install new strobe light and bell c/w wiring, metal conduits and other accessories as per requirements.	sum	

PROPOSED ADDITIONS AND ALTERATIONS WORKS FOR OFFICE OF FOOTBALL ASSOCIATION OF SINGAPORE @ 100 TYRWHITT ROAD, JALAN BESAR STADIUM, SINGAPORE 207542

BILL NO. 2 - SCHEDULE OF OPTIONAL WORKS

ITEM	DESCRIPTION	UNIT	AMOUNT (S\$)
C	MAIN BLOCK LEVEL 2 RIGHT WING TOILETS (MALE / FEMALE)		
C17	To supply and install new EXHAUST AIR fan system c/w silencers on both sides, acoustic box-up, local start / stop panel, power and control wiring, starters, mountings, timer, labelling and all ancillary and accessories as required.	sum	
C18	To supply and install new DUCT works to the above fans c/w flexible connections, access panels, volume control dampers, painting, labelling and all necessary ancillary and accessories. Ducts shall be connected to existing external facing grilles;-	sum	
C19	Supply and install lighting distribution c/w concealed sub-circuit wiring in conduit, switch plates, K.O box and all other ancillaries and accessories for the following areas; * LED recessed downlight fittings. * LED strip light for concealed pelmet in ceiling or furniture	sum	
C20	Supply and install emergency lighting distribution c/w concealed sub-circuit wiring in conduit and all other ancillaries and accessories.	sum	
C21	Supply and install power distribution c/w concealed sub-circuit wiring in conduit, switch plates, K.O box and all other accessories as indicated below; * 1x13amp Switch Socket Outlet for other services	sum	
C22	<p>ANY OTHER WORKS</p> <p>Contractor to price for all other and necessary works (that have been inadvertently left out in the above scope of works) which area deem necessary for the full and proper completion of the project.</p> <p>Please specify below :- (Attached a separate sheet if space is in sufficient)</p> <p>a. _____</p> <p>b. _____</p> <p>c. _____</p>	sum sum sum	
	Total for Level 2 Right Wing Toilets		

PROPOSED ADDITIONS AND ALTERATIONS WORKS FOR OFFICE OF FOOTBALL ASSOCIATION OF SINGAPORE @ 100 TYRWHITT ROAD, JALAN BESAR STADIUM, SINGAPORE 207542

BILL NO. 2 - SCHEDULE OF OPTIONAL WORKS

ITEM	DESCRIPTION	UNIT	AMOUNT (S\$)
D	MAIN BLOCK LEVEL 2 LEFT WING TOILETS (MALE / FEMALE)		
D1	Supply labour, tools, transport and equipment to demolish/ dismantle/ hack away and remove, including all necessary disposal offsite, all unwanted existing <u>floor, walls, ceiling elements / fittings</u> and services to facilitate the construction of proposed new works for the respective phases of construction works.		
D2	Supply and install 150mm thick built-on-edge celcom (light weight block) walls of various height c/w cement plastering on both sides; necessary bonding ties, vertical and horizontal steel stiffener / lintel as shown on drawings	sum	
D3	Supply and install 12mm thick calcium silicate board plaster ceiling for wet areas as shown on drawings.	sum	
D4	Make good existing timber door ; finish in specified laminate including new <u>conceal door closer</u> , lever lockset with master key system and repaint existing hardwood door jamb in spray paint finish as shown on drawings.	sum	
D5	Supply labour, tools and equipment to prepare and plaster all new and existing wall / partitions including all necessary cleaning and making good surfaces prior to the application of new paint works as shown on drawings.	sum	
D6	Supply and apply 1 under coat and minimum 2 finishing coat of various selected weatherproof paint colour to all internal wall / ceiling surface areas as shown on drawings.	sum	
D7	Supply and install new wall tiles for selected wet areas areas c/w matching pointing and any necessary waterproofing up-turn system (All wall surfaces to be covered with tiles including surfaces behind cabinet carcasses)	sum	
D8	Supply labour and materials to re-screed existing floor areas c/w necessary waterproofing system and trowelled smooth of surface to received new floor finishes. Cost include 10 years warranty for waterproofing of the wet areas.(Ponding test to be carried out at all wet areas for minimum 24hrs and witness by PM)	sum	
D9	Supply and install new floor tiles for wet areas areas c/w matching pointing, any necessary waterproofing system and slope to fall. (All floor surface in the above areas including cabinet plinths below cabinet carcasses to be covered with tiles)	sum	

PROPOSED ADDITIONS AND ALTERATIONS WORKS FOR OFFICE OF FOOTBALL ASSOCIATION OF SINGAPORE @ 100 TYRWHITT ROAD, JALAN BESAR STADIUM, SINGAPORE 207542

BILL NO. 2 - SCHEDULE OF OPTIONAL WORKS

ITEM	DESCRIPTION	UNIT	AMOUNT (S\$)
D	MAIN BLOCK LEVEL 2 LEFT WING TOILETS (MALE / FEMALE)		
D10	Supply and install Phenolic board toilet cubicles c/w phenolic boards cubicles and accessories for Male and Female Toilets.	sum	
D11	Supply and install new Door Sign base on Designer's Theme for all internal Doors.Provision of art work for approval by Client; Fabrication / Installation of actual signage on doors.	sum	
D12	Supply and install Vanity cabinet with Mirror including Solid surface top and laminate carcass for Male / Female. (2 sets)	sum	
D13	Supply, delivery and installation of new stainless steel cold-water pipe works c/w private water meter for each pantry, check valves, gate valves, ball valves, water filter and all accessories.	sum	
D14	Supply and install floor wastes, floor traps and connect to sanitary waste pipe located at floor below c/w coring, supports, pipework & fittings as required.	sum	
D15	Supply and install following approved sanitary wares fixtures and fitting c/w all sanitary and plumbing piping works; brackets; and accessories as follow: <u>Male / Female / Handicap Toilet</u> <ul style="list-style-type: none"> * Selected seating type water closet with sensor flush * Selected wall hung wash basin for handicap Toilet * Selected standard size recessed wash basin for vanity counter for both Male & Female Toilets. * Selected sensor water tape for vanity basin for Male, Female & Handicap Toilets * Selected jumbo toilet paper holder * Selected auto sensor hand soap dispenser * Selected hand dryer * Selected bidget spray * Selected standard mirror for handicap toilet. * Selected standard handicap rail bar set * Selected bid tap for washing of toilet. 	sum	
D16	To supply and install new strobe light and bell c/w wiring, metal conduits and other accessories as per requirements.	sum	

PROPOSED ADDITIONS AND ALTERATIONS WORKS FOR OFFICE OF FOOTBALL ASSOCIATION OF SINGAPORE @ 100 TYRWHITT ROAD, JALAN BESAR STADIUM, SINGAPORE 207542

BILL NO. 2 - SCHEDULE OF OPTIONAL WORKS

ITEM	DESCRIPTION	UNIT	AMOUNT (S\$)
D	MAIN BLOCK LEVEL 2 LEFT WING TOILETS (MALE / FEMALE)		
D17	To supply and install new EXHAUST AIR fan system c/w silencers on both sides, acoustic box-up, local start / stop panel, power and control wiring, starters, mountings, timer, labelling and all ancillary and accessories as required.	sum	
D18	To supply and install new DUCT works to the above fans c/w flexible connections, access panels, volume control dampers, painting, labelling and all necessary ancillary and accessories. Ducts shall be connected to existing external facing grilles;-	sum	
D19	Supply and install lighting distribution c/w concealed sub-circuit wiring in conduit, switch plates, K.O box and all other ancillaries and accessories for the following areas; * LED recessed downlight fittings. * LED strip light for concealed pelmet in ceiling or furniture	sum	
D20	Supply and install emergency lighting distribution c/w concealed sub-circuit wiring in conduit and all other ancillaries and accessories.	sum	
D21	Supply and install power distribution c/w concealed sub-circuit wiring in conduit, switch plates, K.O box and all other accessories as indicated below; * 1x13amp Switch Socket Outlet for other services	sum	
D22	<p>ANY OTHER WORKS</p> <p>Contractor to price for all other and necessary works (that have been inadvertently left out in the above scope of works) which area deem necessary for the full and proper completion of the project.</p> <p>Please specify below :- (Attached a separate sheet if space is in sufficient)</p> <p>a. _____</p> <p>b. _____</p> <p>c. _____</p>	sum sum sum	
	Total for Level 2 Left Wing Toilets		

PROPOSED ADDITIONS AND ALTERATIONS WORKS FOR OFFICE OF FOOTBALL ASSOCIATION OF SINGAPORE @ 100 TYRWHITT ROAD, JALAN BESAR STADIUM, SINGAPORE 207542

BILL NO. 2 - SCHEDULE OF OPTIONAL WORKS

ITEM	DESCRIPTION	UNIT	AMOUNT (S\$)
E	ANNEX BLOCK LEVEL 3 TOILETS & SHOWER (MALE / FEMALE / HANDICAP)		
E1	Supply labour, tools, transport and equipment to demolish/ dismantle/ hack away and remove, including all necessary disposal offsite, all unwanted existing <u>floor, walls, ceiling elements / fittings</u> and services to facilitate the construction of proposed new works for the respective phases of construction works.		
E2	Supply and install 150mm thick built-on-edge celcom (light weight block) walls of various height c/w cement plastering on both sides; necessary bonding ties, vertical and horizontal steel stiffener / lintel as shown on drawings	sum	
E3	Supply and install 12mm thick calcium silicate board plaster ceiling for wet areas as shown on drawings.	sum	
E4	Make good existing timber door ; finish in specified laminate including new <u>conceal door closer</u> , lever lockset with master key system and repaint existing hardwood door jamb in spray paint finish as shown on drawings.	sum	
E5	Supply labour, tools and equipment to prepare and plaster all new and existing wall / partitions including all necessary cleaning and making good surfaces prior to the application of new paint works as shown on drawings.	sum	
E6	Supply and apply 1 under coat and minimum 2 finishing coat of various selected weatherproof paint colour to all internal wall / ceiling surface areas as shown on drawings.	sum	
E7	Supply and install new wall tiles for selected wet areas areas c/w matching pointing and any necessary waterproofing up-turn system (All wall surfaces to be covered with tiles including surfaces behind cabinet carcasses)	sum	
E8	Supply labour and materials to re-screed existing floor areas c/w necessary waterproofing system and trowelled smooth of surface to received new floor finishes. Cost include 10 years warranty for waterproofing of the wet areas.(Ponding test to be carried out at all wet areas for minimum 24hrs and witness by PM)	sum	
E9	Supply and install new floor tiles for wet areas areas c/w matching pointing, any necessary waterproofing system and slope to fall. (All floor surface in the above areas including cabinet plinths below cabinet carcasses to be covered with tiles)	sum	

PROPOSED ADDITIONS AND ALTERATIONS WORKS FOR OFFICE OF FOOTBALL ASSOCIATION OF SINGAPORE @ 100 TYRWHITT ROAD, JALAN BESAR STADIUM, SINGAPORE 207542

BILL NO. 2 - SCHEDULE OF OPTIONAL WORKS

ITEM	DESCRIPTION	UNIT	AMOUNT (S\$)
E	ANNEX BLOCK LEVEL 3 TOILETS & SHOWER (MALE / FEMALE / HANDICAP)		
E10	Supply and install Phenolic board toilet cubicles c/w phenolic boards cubicles and accessories for Male and Female Toilets.	sum	
E11	Supply and install new Door Sign base on Designer's Theme for all internal Doors.Provision of art work for approval by Client; Fabrication / Installation of actual signage on doors.	sum	
E12	Supply and install Vanity cabinet with Mirror including Solid surface top and laminate carcass for Male / Female. (2 sets)	sum	
E13	Supply and install Phenolic board locker cabinets c/w number lock and accessories	sum	
E14	Supply, delivery and installation of new stainless steel cold-water pipe works c/w private water meter for each pantry, check valves, gate valves, ball valves, water filter and all accessories.	sum	
E15	Supply and install floor wastes, floor traps and connect to sanitary waste pipe located at floor below c/w coring, supports, pipework & fittings as required.	sum	
E16	Supply and install following approved sanitary wares fixtures and fitting c/w all sanitary and plumbing piping works; brackets; and accessories as follow: <u>Male / Female / Handicap Shower & Toilet</u> * Selected seating type water closet with sensor flush * Selected wall hung wash basin for handicap Toilet * Selected standard size recessed wash basin for vanity counter for both Male & Female Toilets. * Selected sensor water tape for vanity basin for Male, Female & Handicap Toilets * Selected jumbo toilet paper holder * Selected auto sensor hand soap dispenser * Selected hand dryer * Selected bidget spray * Selected standard mirror for handicap toilet. * Selected standard handicap rail bar set * Selected bid tap for washing of toilet.	sum	
E17	To supply and install new strobe light and bell c/w wiring, metal conduits and other accessories as per requirements.	sum	

PROPOSED ADDITIONS AND ALTERATIONS WORKS FOR OFFICE OF FOOTBALL ASSOCIATION OF SINGAPORE @ 100 TYRWHITT ROAD, JALAN BESAR STADIUM, SINGAPORE 207542

BILL NO. 2 - SCHEDULE OF OPTIONAL WORKS

ITEM	DESCRIPTION	UNIT	AMOUNT (S\$)
E	ANNEX BLOCK LEVEL 3 TOILETS & SHOWER (MALE / FEMALE / HANDICAP)		
E18	To supply and install new EXHAUST AIR fan system c/w silencers on both sides, acoustic box-up, local start / stop panel, power and control wiring, starters, mountings, timer, labelling and all ancillary and accessories as required.	sum	
E19	To supply and install new DUCT works to the above fans c/w flexible connections, access panels, volume control dampers, painting, labelling and all necessary ancillary and accessories. Ducts shall be connected to existing external facing grilles;-	sum	
E20	Supply and install lighting distribution c/w concealed sub-circuit wiring in conduit, switch plates, K.O box and all other ancillaries and accessories for the following areas; * LED recessed downlight fittings. * LED strip light for concealed pelmet in ceiling or furniture	sum	
E21	Supply and install emergency lighting distribution c/w concealed sub-circuit wiring in conduit and all other ancillaries and accessories.	sum	
E22	Supply and install power distribution c/w concealed sub-circuit wiring in conduit, switch plates, K.O box and all other accessories as indicated below; * 1x13amp Switch Socket Outlet for other services	sum	
E23	<p>ANY OTHER WORKS</p> <p>Contractor to price for all other and necessary works (that have been inadvertently left out in the above scope of works) which area deem necessary for the full and proper completion of the project.</p> <p>Please specify below :- (Attached a separate sheet if space is in sufficient)</p> <p>a. _____</p> <p>b. _____</p> <p>c. _____</p>	sum sum sum	
	Total for Level 2 Left Wing Toilets		

PROPOSED ADDITIONS AND ALTERATIONS WORKS FOR OFFICE OF FOOTBALL ASSOCIATION OF SINGAPORE @ 100 TYRWHITT ROAD, JALAN BESAR STADIUM, SINGAPORE 207542

BILL NO. 2 - SCHEDULE OF OPTIONAL WORKS

ITEM	DESCRIPTION	UNIT	AMOUNT (S\$)
F	ANNEX BLOCK LEVEL 4 TOILETS (MALE / FEMALE / HANDICAP)		
F1	Supply labour, tools, transport and equipment to demolish/ dismantle/ hack away and remove, including all necessary disposal offsite, all unwanted existing <u>floor, walls, ceiling elements / fittings</u> and services to facilitate the construction of proposed new works for the respective phases of construction works.		
F2	Supply and install 150mm thick built-on-edge celcom (light weight block) walls of various height c/w cement plastering on both sides; necessary bonding ties, vertical and horizontal steel stiffener / lintel as shown on drawings	sum	
F3	Supply and install 12mm thick calcium silicate board plaster ceiling for wet areas as shown on drawings.	sum	
F4	Make good existing timber door ; finish in specified laminate including new <u>conceal door closer</u> , lever lockset with master key system and repaint existing hardwood door jamb in spray paint finish as shown on drawings.	sum	
F5	Supply labour, tools and equipment to prepare and plaster all new and existing wall / partitions including all necessary cleaning and making good surfaces prior to the application of new paint works as shown on drawings.	sum	
F6	Supply and apply 1 under coat and minimum 2 finishing coat of various selected weatherproof paint colour to all internal wall / ceiling surface areas as shown on drawings.	sum	
F7	Supply and install new wall tiles for selected wet areas areas c/w matching pointing and any necessary waterproofing up-turn system (All wall surfaces to be covered with tiles including surfaces behind cabinet carcasses)	sum	
F8	Supply labour and materials to re-screed existing floor areas c/w necessary waterproofing system and trowelled smooth of surface to received new floor finishes. Cost include 10 years warranty for waterproofing of the wet areas.(Ponding test to be carried out at all wet areas for minimum 24hrs and witness by PM)	sum	
F9	Supply and install new floor tiles for wet areas areas c/w matching pointing, any necessary waterproofing system and slope to fall. (All floor surface in the above areas including cabinet plinths below cabinet carcasses to be covered with tiles)	sum	

PROPOSED ADDITIONS AND ALTERATIONS WORKS FOR OFFICE OF FOOTBALL ASSOCIATION OF SINGAPORE @ 100 TYRWHITT ROAD, JALAN BESAR STADIUM, SINGAPORE 207542

BILL NO. 2 - SCHEDULE OF OPTIONAL WORKS

ITEM	DESCRIPTION	UNIT	AMOUNT (S\$)
F	ANNEX BLOCK LEVEL 4 TOILETS (MALE / FEMALE / HANDICAP)		
F10	Supply and install Phenolic board toilet cubicles c/w phenolic boards cubicles and accessories for Male and Female Toilets.	sum	
F11	Supply and install new Door Sign base on Designer's Theme for all internal Doors.Provision of art work for approval by Client; Fabrication / Installation of actual signage on doors.	sum	
F12	Supply and install Vanity cabinet with Mirror including Solid surface top and laminate carcass for Male / Female. (2 sets)	sum	
F13	Supply, delivery and installation of new stainless steel cold-water pipe works c/w private water meter for each pantry, check valves, gate valves, ball valves, water filter and all accessories.	sum	
F14	Supply and install floor wastes, floor traps and connect to sanitary waste pipe located at floor below c/w coring, supports, pipework & fittings as required.	sum	
F15	Supply and install following approved sanitary wares fixtures and fitting c/w all sanitary and plumbing piping works; brackets; and accessories as follow: <u>Male / Female / Handicap Toilet</u> <ul style="list-style-type: none"> * Selected seating type water closet with sensor flush * Selected wall hung wash basin for handicap Toilet * Selected standard size recessed wash basin for vanity counter for both Male & Female Toilets. * Selected sensor water tape for vanity basin for Male, Female & Handicap Toilets * Selected jumbo toilet paper holder * Selected auto sensor hand soap dispenser * Selected hand dryer * Selected bidget spray * Selected standard mirror for handicap toilet. * Selected standard handicap rail bar set * Selected bid tap for washing of toilet. 	sum	
F16	To supply and install new strobe light and bell c/w wiring, metal conduits and other accessories as per requirements.	sum	

PROPOSED ADDITIONS AND ALTERATIONS WORKS FOR OFFICE OF FOOTBALL ASSOCIATION OF SINGAPORE @ 100 TYRWHITT ROAD, JALAN BESAR STADIUM, SINGAPORE 207542

BILL NO. 2 - SCHEDULE OF OPTIONAL WORKS

ITEM	DESCRIPTION	UNIT	AMOUNT (S\$)
F	ANNEX BLOCK LEVEL 4 TOILETS (MALE / FEMALE / HANDICAP)		
F17	To supply and install new EXHAUST AIR fan system c/w silencers on both sides, acoustic box-up, local start / stop panel, power and control wiring, starters, mountings, timer, labelling and all ancillary and accessories as required.	sum	
F18	To supply and install new DUCT works to the above fans c/w flexible connections, access panels, volume control dampers, painting, labelling and all necessary ancillary and accessories. Ducts shall be connected to existing external facing grilles;-	sum	
F19	Supply and install lighting distribution c/w concealed sub-circuit wiring in conduit, switch plates, K.O box and all other ancillaries and accessories for the following areas; * LED recessed downlight fittings. * LED strip light for concealed pelmet in ceiling or furniture	sum	
F20	Supply and install emergency lighting distribution c/w concealed sub-circuit wiring in conduit and all other ancillaries and accessories.	sum	
F21	Supply and install power distribution c/w concealed sub-circuit wiring in conduit, switch plates, K.O box and all other accessories as indicated below; * 1x13amp Switch Socket Outlet for other services	sum	
F22	<p>ANY OTHER WORKS</p> <p>Contractor to price for all other and necessary works (that have been inadvertently left out in the above scope of works) which area deem necessary for the full and proper completion of the project.</p> <p>Please specify below :- (Attached a separate sheet if space is in sufficient)</p> <p>a. _____</p> <p>b. _____</p> <p>c. _____</p>	sum sum sum	
	Total for Level 2 Left Wing Toilets		